EXCEL®



# RESERVE

CARPET PLANK



GREZZO

EXCEL®


# Overview
# FRESH CARPET
# Looks



01 Red




02 Orange



03 Yellow



04 Green



05 Blue



09 Grey

**NOTE**

- Photos are showing only the design patterns.
- The color of the sample pasted is only showing part of the actual carpet.
- Specifications are subject to change when they improve product.
- Slight colour variations may occur from dye lot to dye lot.


02 Orange



03 Yellow & 09 Grey



04 Green & 09 Grey



05 Blue & 09 Grey


09 Grey

## SPECIFICATION

| | |
|---|---|
| Product Name | RESERVE |
| Construction | Multi-level loop |
| Yarn Type | 100% Polypropylene (PP) |
| Dye Method | 100% Solution Dyed |
| Machine Guage | 1/10" |
| Stitches | 10.5 per inch |
| Pile Height | 2.5~6.5mm(±0.5mm) |
| Total thickness | 6.5m (±0.5mm) |
| Pile Weight | 650 g/$m^2$ |
| Total weight | 3400±100 g/$m^2$ |
| Primary Backing | Non Woven Synthetic |
| Second Backing | Bitumen |
| Tile Size | 25cm×100cm |
| Area of use | Heavy commercial |
| Packing | 20 tiles/carton (5sqm/Carton) |
| Flammability | Passes ASTM D2859-16 |
| Smoke Density | Passes ASTM E 662 < 450 |
| Dimensional Stability | ASTM D7570/AACHEN < 0.2% |
| Tuft Bind | ASTMD1335 >7.8 lbs |
| Static Propensity | Passes AATCC-134 < 3.5KV |
| Stain Resistance | AATCC 175-2003 Rating 10 |
| Colorfastness to Crocking | Rating 5, AATCC Test Method 165 |
| Colorfastness to Light | Rating 5, AATCC Test Method 16.3 |
| Indoor Air Quality | CRI Green Label Plus GLP1727 |


## WARRANTIES

**5 YEARS GENERAL WARRANTY**


EXCEL IMPORT PVT LTD hereinafter called EXCEL CLASSIC FLOORS warrants to its customer that all polypropylene carpet tiles IMPORTED by EXCEL IMPORT PVT LTD will be first quality and will be free from manufacturing defects within general accepted standard of industry. If there is a manufacturing defect, a EXCEL representative must be notified immediately by the end user in writing. Written notification must include description of said defects, together with proof of purchase to the party (seller) from whom the product was purchased. Allow 2-4 weeks for processing.

After notification to EXCEL, EXCEL representative will, if necessary, inspect and verify the defect, if such defect is verified, EXCEL will, at its option, arrange for repair or replacement of the defective carpet.


## INSTALLATION METHODS




Herringbone



Ashler



Monolithic



Brick

## DISCLAIMERS

- According to international Carpet manufactured norms color may differ from dye lot to dye lot within tolerance.
- Please take note of the day lot number on the cartons before installing the tiles.
- Recommended laying of Carpet tiles : Checkered board pattern.